BID RESULTS

BID DATE: 1 - 17 - 2001 **CD 11** **{ TWO BIDS RECEIVED }**

BANDERA STREET BULKHEAD (AT BEDEL STREET) W. O. E6000550				CITY ENGINEER'S ESTIMATE				BERYL LOCKHART ENTERPRISES, INC.				CLARKE CONTRACTING CORPORATION			
ITEM NO.	ITEM DESCRIPTION	UNIT	QTY.	UNIT PRICE $	¢	ITEM TOTAL $	¢	UNIT PRICE $	¢	ITEM TOTAL $	¢	UNIT PRICE $	¢	ITEM TOTAL $	¢
1.	Clearing and grubbing, incl. tree removal.	LS				9,003	00			6,000	00			5,000	00
2.	Drill holes for soldier beam pile.	LF	214	60	00	12,840	00	95	33	20,400	62	138	00	29,532	00
3.	Furnish and set in place steel soldier pile, W 21 x 101.	LF	74	63	00	4,662	00	81	40	6,023	60	129	00	9,546	00
4.	Furnish and set in place steel soldier pile, W 21 x 62.	LF	150	46	00	6,900	00	58	11	8,716	50	76	00	11,400	00
5.	Furnish and affix 1/2" thick steel cap plate.	LB	230	7	00	1,610	00	15	05	3,461	50	8	00	1,840	00
6.	Furnish and place concrete encasement for steel soldier piles (560-C-3250).	CY	23	150	00	3,450	00	131	96	3,035	08	133	00	3,059	00
7.	Furnish and place slurry beneath concrete panels (100-E-100).	CY	2	150	00	300	00	1,662	50	3,325	00	179	00	358	00
8.	Furnish and set in place 6" thick precast 3,250 psi concrete lagging panel.	SF	776	40	00	31,040	00	15	00	11,640	00	31	00	24,056	00
9.	Metal guardrail, modified Std. Plan S-462-2.	LF	71	75	00	5,325	00	45	00	3,195	00	59	00	4,189	00
10.	Unclassified excavation.	CY	19	40	00	760	00	113	16	2,150	04	51	00	969	00
11.	Remove and dispose of unsuitable excavation.	CY	20	40	00	800	00	107	50	2,150	00	38	00	760	00
12.	Structural excavation.	CY	240	40	00	9,600	00	32	09	7,701	60	35	00	8,400	00
13.	Structural backfill (may require minor import).	CY	260	20	00	5,200	00	33	47	8,702	20	44	00	11,440	00
14.	4" crushed agregate base.	SF	1,500	2	00	3,000	00	2	35	3,525	00	2	50	3,750	00
15.	4" asphalt pavement (also approximately 2.25 tons of 3" pavement)	TN	40	135	00	5,400	00	95	00	3,800	00	143	00	5,720	00
16.	Conc. integral curb and gutter, Type "C" (a=1', b=8").	LF	67	30	00	2,010	00	29	48	1,975	16	54	00	3,618	00
17.	Traffic control, incl. signs.	LS				8,600	00			3,500	00			3,800	00
18.	Landscaping.	LS				2,500	00			2,826	00			7,500	00
TOTAL BID AMOUNT						**$113,000.00**		**{ 1 }**		**$102,127.30**				**$134,937.00**	
								{ LOW }		**-9.62%**		**{ HIGH }**		**19.41%**	

{ 1 } BERYL LOCKHART ENTERPRISES listed an incorrect ITEM TOTAL for bid items #2 thru #6, #10, #12, #13 and #16 and an incorrect TOTAL BID AMOUNT of $102,120.00 .
The B. O. E. calculated the correct amounts per INSTRUCTIONS TO BIDDERS. Ms. Llynn Lewis of BERYL LOCKHART was informed of these corrections on January 18; she acknowledged and concu

NOTE : The corrections did not change the order of the bids .